BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI

Office of the Executive Engineer Dasarahalli Division,

Schedule-B

NAME OF WORK: Filling of pot holes CC road main road and cross in ward 15

Sl. No	Description of work	Unit	Qty	Rate quoted by the Contractor AVINASH N RAO (SRI AADHITRI CONSULTANCY AND ENGINEERING WORKS)	
				In Figures (Rs.)	Amount
1	2	3	4	5	7
1	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @180 kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications	Cum	76.20	4597.0	350291.40
2	Cement Concrete Pavement :- Construction of un-reinforced, dowel jointed, plain cement concrete pavement over a prepared sub base with 43 grade cement design mix M40 at 420 kg/cum Cement, C.A, 0.67 cum, F.A/ 0.44 cum and down size graded granite metal coarse aggregate at 0.69 cum and fine aggregates @ 0.46 cum with superplastizer at 3lts conforming to IS 9103-1999 reaffirmed 2008. coarse and fine aggregate conforming to IS:383, mixed in a batching and mixing plant as per approved mix design, transported to site, laid with a fixed form or slip form paver, spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, sealant primer, joint sealant, debonding strip, dowel bar, tie rod, admixtures as approved, curing, compound, finishing to lines and grades as per drawing complete as per specifications	Cum	76.20	4920.0	374904.00

Signature of the Contractor

Executive Engineer
Dasarahalli Division,

EXECUTIVE ENGINEER
Bruhat Bengaluru Mahangara Palike,
Dasarahalli Division, Bengaluru-57

Signature of the Contractor

Executive Engineer
Dasarahalli Division
BBMP